

Symons Recreation Complex

Install LVP Flooring

GENERAL

Furnish labor, material and equipment necessary to install new LVP flooring in the exercise room on the Owner's premises at 1250 Symons Circle Richland Center, WI.

SCOPE OF WORK

1. Symons Staff will remove exercise equipment
2. Removal of existing rubber floor. Symons Staff will dispose of rubber flooring
3. Prepare/clean floor in the exercise room
4. Installation of owner selected LVP flooring.
5. The area is roughly 1,556 square feet
6. Direct glue, 20 mill wear layer, aluminized oxide finish
7. Provide transition strip at doorways, if needed
8. Install 6 in base cove.
9. Work must be completed May 18-21, 2020 This is the only time that is available.

NOTES

Bids shall be received prior to May 11, 2020 at 5:00p.m. Bids can be emailed to denise@symonsrec.com or mailed to Denise Lins, Symons Recreation Complex 1250 Symons Circle Richland Center, WI 53581

Richland County reserves the right to accept or reject any or all bids.